

STONE CONSTRUCTION SERVICES, INC.
QUOTE BY TYPE OF WORK

RUN DATE 05/25/2006

Page 1 of 11

ESTIMATE: Kitchen Remodel

FOR:	Craig Mac Kathy Mac 4321 E. 13th. St. Wapahoe, OR 98002	HOME: (555) 987-6543 FAX: (555) 333-2469 CELL 1: (555) 123-6754 CELL 2: (555) 121-2234	BUS.: (555) 333-2468 2nd BUS: (555) 333-2468
------	--	---	---

ITEM #	----- DESCRIPTION -----						
UNIT	UOM	LABOR	MATERIAL	SUB	OTHER	TOTAL	
12	PLANS						
12.330	Plans.....Kitchen						
2.00	PAGE	\$450.00	\$15.00	\$0.00	\$0.00	\$465.00	
TOTAL BY		\$450.00	\$15.00	\$0.00	\$0.00	\$465.00	
13	PERMITS/FEES/ENG.						
13.120	Permit.....By Contractor						
1.00	EA	\$150.00	\$45.00	\$0.00	\$547.50	\$742.50	
TOTAL BY		\$150.00	\$45.00	\$0.00	\$547.50	\$742.50	
14	INSURANCE/BONDS						
14.120	Insurance.....Builders Risk @ 2.5% of S.P.						
30.00	\$1000	\$1,125.00	\$0.00	\$0.00	\$900.00	\$2,025.00	
14.130	Insurance.....Job Coverage						
30.00	\$1000	\$1,125.00	\$0.00	\$0.00	\$450.00	\$1,575.00	
TOTAL BY		\$2,250.00	\$0.00	\$0.00	\$1,350.00	\$3,600.00	
19	MISCELLANEOUS						
19.520	Travel time.....Materials pickup & delivery						
12.00	HR	\$360.00	\$0.00	\$0.00	\$0.00	\$360.00	
19.910	Port-A-Potty.....Rental, per month, recycle weekly						
2.00	MNTH	\$0.00	\$0.00	\$270.00	\$0.00	\$270.00	
TOTAL BY		\$360.00	\$0.00	\$270.00	\$0.00	\$630.00	
22	EXTERIOR DEMOLITION						
22.1430	T/O existing window, up to 5' x 3'						
2.00	EA	\$56.25	\$0.00	\$0.00	\$0.00	\$56.25	
22.1514	T/O exterior opening for new window, reframe 21 to 30 SF						
40.00	SF	\$975.00	\$300.04	\$0.00	\$0.00	\$1,275.04	
22.1520	T/O exterior opening for new window, reframe over 41 SF						
48.00	SF	\$1,080.00	\$360.00	\$0.00	\$0.00	\$1,440.00	
TOTAL BY		\$2,111.25	\$660.04	\$0.00	\$0.00	\$2,771.29	

STONE CONSTRUCTION SERVICES, INC.
QUOTE BY TYPE OF WORK

RUN DATE 05/25/2006

Page 2 of 11

ITEM #	UNIT	UOM	LABOR	MATERIAL	SUB	OTHER	TOTAL
23 INTERIOR DEMOLITION							
23.110							
	300.00	SF	\$123.75	\$36.09	\$0.00	\$0.00	\$159.84
23.150							
	400.00	SF	\$117.00	\$154.92	\$0.00	\$0.00	\$271.92
23.260							
	320.00	SF	\$360.00	\$0.00	\$0.00	\$0.00	\$360.00
23.1430							
	10.00	LF	\$656.25	\$205.23	\$0.00	\$0.00	\$861.48
23.2650							
	30.00	LF	\$117.00	\$0.00	\$0.00	\$0.00	\$117.00
23.2820							
	4.00	EA	\$0.00	\$0.00	\$180.00	\$0.00	\$180.00
23.2830							
	3.00	EA	\$56.25	\$0.00	\$0.00	\$0.00	\$56.25
23.2910							
	2.00	EA	\$0.00	\$0.00	\$225.00	\$0.00	\$225.00
23.3140							
	12.00	LF	\$56.25	\$0.00	\$0.00	\$0.00	\$56.25
23.3240							
	8.00	LF	\$37.50	\$0.00	\$0.00	\$0.00	\$37.50
23.3440							
	320.00	SF	\$360.00	\$0.00	\$0.00	\$0.00	\$360.00
23.4370							
	98.00	SF	\$826.88	\$0.00	\$0.00	\$0.00	\$826.88
23.5110							
	168.00	SF	\$0.00	\$20.16	\$189.00	\$0.00	\$209.16
TOTAL BY			\$2,710.88	\$416.40	\$594.00	\$0.00	\$3,721.28
62 FLOOR							
62.350							
	120.00	SF	\$918.00	\$560.23	\$0.00	\$0.00	\$1,478.23
62.1340							
	320.00	SF	\$480.00	\$346.22	\$0.00	\$0.00	\$826.22
62.1410							
	12.00	SF	\$13.50	\$12.56	\$0.00	\$0.00	\$26.06
TOTAL BY			\$1,411.50	\$919.02	\$0.00	\$0.00	\$2,330.52
64 INTERIOR WALL							
64.310							
	3.00	LF	\$50.63	\$26.07	\$0.00	\$0.00	\$76.70
64.510							
	1.00	EA	\$28.13	\$14.64	\$0.00	\$0.00	\$42.77
TOTAL BY			\$78.75	\$40.72	\$0.00	\$0.00	\$119.47

STONE CONSTRUCTION SERVICES, INC.
QUOTE BY TYPE OF WORK

RUN DATE 05/25/2006

Page 3 of 11

ITEM #	UNIT	UOM	LABOR	MATERIAL	SUB	OTHER	TOTAL
65 CEILING							
65.1710		12" x 12" bulkhead or soffit					
21.00	LF		\$236.25	\$70.79	\$0.00	\$0.00	\$307.04
65.2810		Frame skylight well, 4' wall, dbl flare up to 96 SF of wall area					
96.00	SF		\$849.60	\$316.74	\$0.00	\$0.00	\$1,166.34
TOTAL BY			\$1,085.85	\$387.54	\$0.00	\$0.00	\$1,473.39
88 REPAIRS							
88.110		Patch siding around new window or door, 1/2" x 6" bev cedar					
232.00	SF		\$426.30	\$1,300.20	\$0.00	\$0.00	\$1,726.50
TOTAL BY			\$426.30	\$1,300.20	\$0.00	\$0.00	\$1,726.50
89 MISC.							
89.110		Caulking around windows/doors, joints					
110.00	LF		\$33.00	\$0.92	\$0.00	\$0.00	\$33.92
TOTAL BY			\$33.00	\$0.92	\$0.00	\$0.00	\$33.92
94 VINYL							
94.2110		8' 0" x 4' 0" PF, white, low-E					
1.00	EA		\$135.00	\$336.68	\$0.00	\$0.00	\$471.68
TOTAL BY			\$135.00	\$336.68	\$0.00	\$0.00	\$471.68
96 BAY & BOW							
96.110		6' 4" x 5' 0" bay, 30 degree, XOOX, primed w/screens					
1.00	EA		\$540.00	\$2,561.25	\$0.00	\$0.00	\$3,101.25
TOTAL BY			\$540.00	\$2,561.25	\$0.00	\$0.00	\$3,101.25
97 SKYLIGHTS/GARDEN							
97.710		2' x 4' DG, vinyl, low-E openable					
2.00	EA		\$75.00	\$630.68	\$0.00	\$0.00	\$705.68
97.1530		Roller shade w/handle					
1.00	EA		\$52.50	\$0.00	\$120.00	\$0.00	\$172.50
TOTAL BY			\$127.50	\$630.68	\$120.00	\$0.00	\$878.18
104 INTERIOR							
104.1120		2' 8" x 6' 8" PH, PKT, flush, hc, birch, w/hrdwr & trim					
1.00	EA		\$78.75	\$186.75	\$0.00	\$0.00	\$265.50
104.1740		6' 0" x 6' 8" PH, 1/2 luv, fir, w/hrdwr & trim					
1.00	EA		\$78.75	\$387.75	\$0.00	\$0.00	\$466.50
TOTAL BY			\$157.50	\$574.50	\$0.00	\$0.00	\$732.00
114 FLASHING							
114.550		Roof to wall flashing, 12" stock, include siding cut & renail					
12.00	LF		\$90.00	\$26.53	\$0.00	\$0.00	\$116.53
114.710		Galvanized 28 ga. flashing on exterior of new skylight					
24.00	LF		\$189.00	\$53.06	\$0.00	\$0.00	\$242.06
TOTAL BY			\$279.00	\$79.60	\$0.00	\$0.00	\$358.60

STONE CONSTRUCTION SERVICES, INC.
QUOTE BY TYPE OF WORK

RUN DATE 05/25/2006

Page 4 of 11

ITEM #	UNIT	UOM	DESCRIPTION				TOTAL
			LABOR	MATERIAL	SUB	OTHER	
116 VENTING							
116.230		6" - 7" AL/GALV. vent pipe down draft cooktop, MAX - 12'					
14.00	LF		\$0.00	\$0.00	\$199.50	\$0.00	\$199.50
TOTAL BY			\$0.00	\$0.00	\$199.50	\$0.00	\$199.50
123 ROUGH-IN							
123.710		RI new kitchen sink					
1.00	EA		\$0.00	\$0.00	\$367.50	\$0.00	\$367.50
123.750		RI new kitchen bar sink					
1.00	EA		\$0.00	\$0.00	\$367.50	\$0.00	\$367.50
123.810		RI H2O line for refer					
1.00	EA		\$0.00	\$0.00	\$187.50	\$0.00	\$187.50
TOTAL BY			\$0.00	\$0.00	\$922.50	\$0.00	\$922.50
124 FINISH/RESET							
124.1760		21" x 32" C.I. COLOR sink w/chrome faucet, spray, and trim					
1.00	EA		\$0.00	\$0.00	\$750.00	\$0.00	\$750.00
124.2130		Install new dishwasher & disposal with new sink					
1.00	EA		\$0.00	\$0.00	\$262.50	\$0.00	\$262.50
124.2210		Install new soap dispenser on new sink					
1.00	EA		\$0.00	\$0.00	\$67.50	\$0.00	\$67.50
124.2250		Install new air switch for new disposal					
1.00	EA		\$0.00	\$0.00	\$135.00	\$0.00	\$135.00
124.2720		12" x 12" COLOR fbrgls bar sink w/chrome faucet					
1.00	EA		\$0.00	\$0.00	\$375.00	\$0.00	\$375.00
TOTAL BY			\$0.00	\$0.00	\$1,590.00	\$0.00	\$1,590.00
133 METER & PANEL							
133.310		New 200 amp, 24 circuit panel					
1.00	EA		\$0.00	\$0.00	\$1,800.00	\$0.00	\$1,800.00
TOTAL BY			\$0.00	\$0.00	\$1,800.00	\$0.00	\$1,800.00
134 OUTLETS & SWITCHES							
134.1920		110v GFCI outlet over 30' from panel					
40.00	LF		\$0.00	\$0.00	\$180.00	\$0.00	\$180.00
134.2520		110v smoke detect. over 30' from panel					
1.00	EA		\$0.00	\$0.00	\$3.00	\$0.00	\$3.00
134.3010		110v duplex outlet fished in, added to exist. circuit					
4.00	EA		\$0.00	\$0.00	\$270.00	\$0.00	\$270.00
TOTAL BY			\$0.00	\$0.00	\$453.00	\$0.00	\$453.00
135 LIGHTING & FANS							
135.1820		110v recessed can over 30' from panel MA @ \$40.00					
12.00	LF		\$0.00	\$720.00	\$31.50	\$0.00	\$751.50
TOTAL BY			\$0.00	\$720.00	\$31.50	\$0.00	\$751.50

STONE CONSTRUCTION SERVICES, INC.
QUOTE BY TYPE OF WORK

RUN DATE 05/25/2006

Page 5 of 11

ITEM #	DESCRIPTION						TOTAL
UNIT	UOM	LABOR	MATERIAL	SUB	OTHER		
136 APPLIANCE CIRCUITS							
136.1520	110v. x 20a. dishwasher						
1.00	EA	\$0.00	\$0.00	\$67.50	\$0.00	\$67.50	
136.1540	110v. x 15a. disposal w/wall switch						
1.00	EA	\$0.00	\$0.00	\$112.50	\$0.00	\$112.50	
136.1550	110v. x 15a. hot water maker at sink						
1.00	EA	\$0.00	\$0.00	\$82.50	\$0.00	\$82.50	
136.1610	110v. x 20a. refrigerator						
1.00	EA	\$0.00	\$0.00	\$67.50	\$0.00	\$67.50	
136.1710	110v. x 15a. exhaust hood						
1.00	EA	\$0.00	\$0.00	\$67.50	\$0.00	\$67.50	
136.1810	110v. x 15a. microwave						
1.00	EA	\$0.00	\$0.00	\$67.50	\$0.00	\$67.50	
136.2110	220v. x 60a. range, oven, or cooktop						
1.00	EA	\$0.00	\$0.00	\$105.00	\$0.00	\$105.00	
TOTAL BY		\$0.00	\$0.00	\$570.00	\$0.00	\$570.00	
139 MISC.							
139.920	New ground line from panel to ext. new ground rod						
1.00	EA	\$0.00	\$0.00	\$300.00	\$0.00	\$300.00	
139.1710	Telephone outlet, minimum installation						
1.00	EA	\$0.00	\$0.00	\$112.50	\$0.00	\$112.50	
139.1920	Reroute 110v. circuit around new skylight well to new junction box						
4.00	EA	\$0.00	\$0.00	\$330.00	\$0.00	\$330.00	
139.1960	Reroute 110v. circuit around new window or door opening						
1.00	EA	\$0.00	\$0.00	\$187.50	\$0.00	\$187.50	
139.2550	Cable T.V. outlet, minimum installation						
1.00	EA	\$0.00	\$0.00	\$225.00	\$0.00	\$225.00	
TOTAL BY		\$0.00	\$0.00	\$1,155.00	\$0.00	\$1,155.00	
143 FORCED AIR SYSTEMS							
143.120	Extend 5" - 8" warm air duct, up to 20'						
40.00	LF	\$0.00	\$0.00	\$450.00	\$0.00	\$450.00	
TOTAL BY		\$0.00	\$0.00	\$450.00	\$0.00	\$450.00	
153 BLANKET							
153.1730	3 1/2" R-11 unfaced batts						
256.00	SF	\$0.00	\$0.00	\$115.20	\$0.00	\$115.20	
TOTAL BY		\$0.00	\$0.00	\$115.20	\$0.00	\$115.20	
154 BLOWN-IN							
154.970	Blown-in R-38 fbrgls, 17.75" thick, 40 SF/bag						
320.00	SF	\$0.00	\$0.00	\$336.00	\$0.00	\$336.00	
TOTAL BY		\$0.00	\$0.00	\$336.00	\$0.00	\$336.00	

STONE CONSTRUCTION SERVICES, INC.
QUOTE BY TYPE OF WORK

RUN DATE 05/25/2006

Page 6 of 11

ITEM #	----- DESCRIPTION -----						
UNIT	UOM	LABOR	MATERIAL	SUB	OTHER	TOTAL	
164	INTERIOR DRYWALL						
164.520	Wall, 1/2" N.& T. machine text. O.P.			500 - 1000 SF			
512.00	SF	\$0.00	\$0.00	\$1,305.60	\$0.00	\$1,305.60	
164.3520	Ceiling, 1/2" N.& T. machine text. O.P.			500 - 1000 SF			
320.00	SF	\$0.00	\$0.00	\$864.00	\$0.00	\$864.00	
TOTAL BY		\$0.00	\$0.00	\$2,169.60	\$0.00	\$2,169.60	
169	MISC.						
169.930	Skylit-Dbf.Flr, 1/2" N.& T.mach.brocade			20 - 180 SF			
96.00	SF	\$0.00	\$0.00	\$424.80	\$0.00	\$424.80	
TOTAL BY		\$0.00	\$0.00	\$424.80	\$0.00	\$424.80	

STONE CONSTRUCTION SERVICES, INC.
QUOTE BY TYPE OF WORK

RUN DATE 05/25/2006

Page 7 of 11

ITEM #	----- DESCRIPTION -----						TOTAL
UNIT	UOM	LABOR	MATERIAL	SUB	OTHER		
183	CUSTOM						
183.110	Base cabinet						
14.00	LF	\$0.00	\$0.00	\$1,365.00	\$0.00	\$1,365.00	
183.120	Base drawer, 3 drawer						
1.50	LF	\$0.00	\$0.00	\$171.00	\$0.00	\$171.00	
183.130	Base drawer, 4 drawer						
3.50	LF	\$0.00	\$0.00	\$420.00	\$0.00	\$420.00	
183.140	Base sink						
3.00	LF	\$0.00	\$0.00	\$292.50	\$0.00	\$292.50	
183.150	Base corner						
3.00	LF	\$0.00	\$0.00	\$292.50	\$0.00	\$292.50	
183.160	Base corner Lazy Susan						
3.00	LF	\$0.00	\$0.00	\$360.00	\$0.00	\$360.00	
183.910	Wall cabinet 30" high						
12.00	LF	\$0.00	\$0.00	\$864.00	\$0.00	\$864.00	
183.940	Wall cabinet 18" high						
6.00	LF	\$0.00	\$0.00	\$432.00	\$0.00	\$432.00	
183.960	Wall cabinet 24" high						
2.00	LF	\$0.00	\$0.00	\$144.00	\$0.00	\$144.00	
183.970	Wall corner cabinet 30" high						
2.00	LF	\$0.00	\$0.00	\$144.00	\$0.00	\$144.00	
183.980	Wall corner Lazy Susan 30" high						
2.00	LF	\$0.00	\$0.00	\$165.00	\$0.00	\$165.00	
183.2110	Oven wall cabinet 84" high x 24" deep						
2.50	LF	\$0.00	\$0.00	\$487.50	\$0.00	\$487.50	
183.2910	Bread board, pull out 1" x 21"						
2.00	LF	\$0.00	\$0.00	\$36.00	\$0.00	\$36.00	
183.3310	Drawer & pull out tray/shelf hardware, full extension						
4.00	EA	\$0.00	\$0.00	\$360.00	\$0.00	\$360.00	
183.3320	Sink tilt out tray 12" to 24"						
2.00	EA	\$0.00	\$0.00	\$105.00	\$0.00	\$105.00	
183.3940	Molding, crown						
36.00	LF	\$0.00	\$0.00	\$216.00	\$0.00	\$216.00	
183.4010	Toe kick skins, 1/8" to 1/4", up to 4" high						
28.00	LF	\$0.00	\$0.00	\$105.00	\$0.00	\$105.00	
183.4050	End panels, base						
12.00	SF	\$0.00	\$0.00	\$135.00	\$0.00	\$135.00	
183.4060	End panels, upper						
12.00	SF	\$0.00	\$0.00	\$135.00	\$0.00	\$135.00	
183.4070	End panels, full height						
24.00	SF	\$0.00	\$0.00	\$216.00	\$0.00	\$216.00	
183.4510	Tray dividers, base, 2 per ft.						
2.00	LF	\$0.00	\$0.00	\$105.00	\$0.00	\$105.00	
183.4540	Spice drawers, up to 18" wide						
1.00	EA	\$0.00	\$0.00	\$22.50	\$0.00	\$22.50	
183.4550	Trash baskets, pull out						
1.00	EA	\$0.00	\$0.00	\$67.50	\$0.00	\$67.50	

STONE CONSTRUCTION SERVICES, INC.
QUOTE BY TYPE OF WORK

RUN DATE 05/25/2006

Page 8 of 11

ITEM #	DESCRIPTION						TOTAL
UNIT	UOM	LABOR	MATERIAL	SUB	OTHER		
183.4560	Cutlery dividers, per drawer						
4.00	EA	\$0.00	\$0.00	\$90.00	\$0.00		\$90.00
TOTAL BY		\$0.00	\$0.00	\$6,730.50	\$0.00		\$6,730.50
185	HARDWARE & PULLS						
185.130	Pulls, door & drawer, installed, MAA @ \$ 7.50						
34.00	EA	\$446.25	\$382.50	\$0.00	\$0.00		\$828.75
TOTAL BY		\$446.25	\$382.50	\$0.00	\$0.00		\$828.75
186	INSTALLATION						
186.2510	Customize cab. for range, oven, microwave (NO MATERIALS)						
1.00	EA	\$131.25	\$0.00	\$0.00	\$0.00		\$131.25
TOTAL BY		\$131.25	\$0.00	\$0.00	\$0.00		\$131.25
189	MISC.						
189.910	Bench seat, 18" high x 24" deep, recessed panel design						
6.00	LF	\$0.00	\$0.00	\$855.00	\$0.00		\$855.00
189.1110	Glass insert in wall cabinet door, IAA @ \$45.00 ea.						
4.00	EA	\$0.00	\$0.00	\$270.00	\$0.00		\$270.00
TOTAL BY		\$0.00	\$0.00	\$1,125.00	\$0.00		\$1,125.00
195	SOLID SURFACE - COOKING AREA						
195.730	Granite, 25 1/4" deep, 4" splash, IAA @ \$130.00 S.F.						
60.00	SF	\$0.00	\$0.00	\$11,700.00	\$0.00		\$11,700.00
TOTAL BY		\$0.00	\$0.00	\$11,700.00	\$0.00		\$11,700.00
204	WALL COVERINGS						
204.540	4 1/4" x 4 1/4" mud set, MA @ \$4.50 SF						
20.00	SF	\$0.00	\$0.00	\$645.00	\$0.00		\$645.00
TOTAL BY		\$0.00	\$0.00	\$645.00	\$0.00		\$645.00
213	SHEET MATERIALS						
213.150	Install 6' Sheet vinyl, MA @ \$30.00 SY						
13.50	SY	\$0.00	\$0.00	\$769.50	\$0.00		\$769.50
TOTAL BY		\$0.00	\$0.00	\$769.50	\$0.00		\$769.50
217	BASE						
217.120	4" high rubber base, all colors						
54.00	LF	\$0.00	\$0.00	\$133.65	\$0.00		\$133.65
TOTAL BY		\$0.00	\$0.00	\$133.65	\$0.00		\$133.65
224	KITCHEN						
224.110	F&I towel bar, 18" to 24" chrome, MAA @ \$7.50						
1.00	EA	\$13.13	\$11.25	\$0.00	\$0.00		\$24.38
224.310	F&I paper towel dispenser, MAA @ \$7.50						
1.00	EA	\$10.50	\$11.25	\$0.00	\$0.00		\$21.75
TOTAL BY		\$23.63	\$22.50	\$0.00	\$0.00		\$46.13

STONE CONSTRUCTION SERVICES, INC.
QUOTE BY TYPE OF WORK

RUN DATE 05/25/2006

Page 9 of 11

ITEM #	----- DESCRIPTION -----						TOTAL
UNIT	UOM	LABOR	MATERIAL	SUB	OTHER		
225	APPLIANCES						
225.140	Dishwasher	MAA @ \$ 850					
1.00	EA	\$0.00	\$0.00	\$0.00	\$1,275.00	\$1,275.00	
225.160	Disposal, 3/4 HP	MAA @ \$ 200					
1.00	EA	\$0.00	\$0.00	\$0.00	\$300.00	\$300.00	
225.170	Hood 30"	MAA @ \$ 175					
1.00	EA	\$0.00	\$0.00	\$0.00	\$262.50	\$262.50	
225.180	Instant Hot H2O	MAA @ \$ 150 (1 Gal.)					
1.00	EA	\$0.00	\$0.00	\$0.00	\$225.00	\$225.00	
225.190	Microwave Oven	MAA @ \$ 225 (Deck)					
1.00	EA	\$0.00	\$0.00	\$0.00	\$337.50	\$337.50	
225.230	Wall Oven, Dbl.	MAA @ \$1,700					
1.00	EA	\$0.00	\$0.00	\$0.00	\$2,550.00	\$2,550.00	
225.270	Range, Slide In	MAA @ \$1,200 (Elect.)					
1.00	EA	\$0.00	\$0.00	\$0.00	\$1,800.00	\$1,800.00	
225.320	Refer, Dbl. door	MAA @ \$1,200 (18 - 22 C.F. w/Ice & H2O)					
1.00	EA	\$0.00	\$0.00	\$0.00	\$1,800.00	\$1,800.00	
225.930	U&I Dishwasher	no plumbing or electrical					
1.00	EA	\$26.25	\$0.00	\$0.00	\$0.00	\$26.25	
225.940	U&I Disposal,	no electrical					
1.00	EA	\$97.50	\$0.00	\$0.00	\$0.00	\$97.50	
225.950	U&I Hood	no electric or venting					
1.00	EA	\$52.50	\$0.00	\$0.00	\$0.00	\$52.50	
225.960	U&I Microwave	no electric					
1.00	EA	\$52.50	\$0.00	\$0.00	\$0.00	\$52.50	
225.980	U&I Oven, DBL.	no gas or electric					
1.00	EA	\$65.63	\$0.00	\$0.00	\$0.00	\$65.63	
225.990	U&I Range	no gas or electric					
1.00	EA	\$52.50	\$0.00	\$0.00	\$0.00	\$52.50	
225.1010	U&I Refer	no electric or H2O					
1.00	EA	\$52.50	\$0.00	\$0.00	\$0.00	\$52.50	
TOTAL BY		\$399.38	\$0.00	\$0.00	\$8,550.00	\$8,949.38	
229	MISC.						
229.610	NEW auxiliary booster fan for cooktop, IAA @ \$650.00						
1.00	EA	\$0.00	\$0.00	\$1,012.50	\$0.00	\$1,012.50	
TOTAL BY		\$0.00	\$0.00	\$1,012.50	\$0.00	\$1,012.50	

STONE CONSTRUCTION SERVICES, INC.
QUOTE BY TYPE OF WORK

RUN DATE 05/25/2006

Page 10 of 11

ITEM #	----- DESCRIPTION -----						TOTAL
UNIT	UOM	LABOR	MATERIAL	SUB	OTHER		
244	INTERIOR MOLDING/TRIM						
244.120	1" x 5" surround & 7/16" x 1 1/2" casing on window						
44.00	LF	\$69.30	\$48.93	\$0.00	\$0.00	\$118.23	
244.520	1" x 5" surround & 7/16" x 1 1/2" casing on door						
17.00	LF	\$26.78	\$18.91	\$0.00	\$0.00	\$45.68	
244.4920	1" x 5" red/white oak threshold, 6", cut/beveled to fit, unfinished						
6.00	LF	\$157.50	\$346.50	\$0.00	\$0.00	\$504.00	
244.6510	1" x 6" surround & 7/16" x 1 1/2" casing on BAY / BOW window						
36.00	SF	\$85.05	\$45.24	\$0.00	\$0.00	\$130.29	
244.6550	1" MDF seat for BAY / BOW window						
12.00	SF	\$18.90	\$15.08	\$0.00	\$0.00	\$33.98	
TOTAL BY		\$357.53	\$474.65	\$0.00	\$0.00	\$832.18	
249	MISC.						
249.1920	1" x 5" surround or banding in skylight well						
32.00	LF	\$134.40	\$6.55	\$0.00	\$0.00	\$140.95	
TOTAL BY		\$134.40	\$6.55	\$0.00	\$0.00	\$140.95	
251	SUBS/MATERIALS						
251.510	Misc. mechanical hardware for KITCHEN remodel 0 - \$20,000						
47.00	\$1000	\$0.00	\$0.00	\$0.00	\$2,467.50	\$2,467.50	
TOTAL BY		\$0.00	\$0.00	\$0.00	\$2,467.50	\$2,467.50	
275	INTERIOR						
275.510	Recessed fixture MA @ \$75.00 fixture, installed						
12.00	EA	\$877.50	\$1,350.00	\$0.00	\$0.00	\$2,227.50	
TOTAL BY		\$877.50	\$1,350.00	\$0.00	\$0.00	\$2,227.50	
284	INTERIOR PREP.						
284.2510	Sand and fill, doors, windows, trim, LIGHT						
36.00	SF	\$0.00	\$0.00	\$24.30	\$0.00	\$24.30	
284.3720	Mask off with 12" paper and 1" masking tape						
60.00	LF	\$0.00	\$0.00	\$10.80	\$0.00	\$10.80	
284.3810	Plastic on walls and openings, 1 mil., 8' high						
300.00	LF	\$0.00	\$0.00	\$337.50	\$0.00	\$337.50	
284.3820	Plastic on ceiling and openings, 1 mil.						
320.00	SF	\$0.00	\$0.00	\$48.00	\$0.00	\$48.00	
TOTAL BY		\$0.00	\$0.00	\$420.60	\$0.00	\$420.60	
285	INTERIOR						
285.910	1 coat primer sprayed and brushed out						
525.00	SF	\$0.00	\$0.00	\$236.25	\$0.00	\$236.25	
285.2520	2 coat oil paint sprayed and brushed out						
525.00	SF	\$0.00	\$0.00	\$433.13	\$0.00	\$433.13	
TOTAL BY		\$0.00	\$0.00	\$669.38	\$0.00	\$669.38	

STONE CONSTRUCTION SERVICES, INC.
QUOTE BY TYPE OF WORK

RUN DATE 05/25/2006

Page 11 of 11

ITEM #	----- DESCRIPTION -----						TOTAL
UNIT	UOM	LABOR	MATERIAL	SUB	OTHER		
286	SPECIALTY/SKYLIGHTS						
286.920	Skylight well, 1 coat primer, rolled and brushed out						
96.00	SF	\$0.00	\$0.00	\$72.00	\$0.00	\$72.00	
286.1040	Skylight well, 2 coats oil paint, rolled and brushed out						
96.00	SF	\$0.00	\$0.00	\$129.60	\$0.00	\$129.60	
TOTAL BY		\$0.00	\$0.00	\$201.60	\$0.00	\$201.60	
295	INTERIOR JOB - 1 STORY						
295.550	Kitchen misc. cleanup \$60,001 - \$76,000						
48.00	\$1000	\$324.00	\$0.00	\$0.00	\$0.00	\$324.00	
TOTAL BY		\$324.00	\$0.00	\$0.00	\$0.00	\$324.00	
305	INTERIOR JOB - 1 STORY						
305.150	Kitchen \$60,001 - \$75,000						
48.00	\$1000	\$0.00	\$0.00	\$0.00	\$2,160.00	\$2,160.00	
TOTAL BY		\$0.00	\$0.00	\$0.00	\$2,160.00	\$2,160.00	
=====							
JOB TOTAL		\$15,000.45	\$10,923.72	\$34,608.83	\$15,075.00	\$75,608.00	
TAX		\$0.00	\$0.00	\$0.00	\$0.00	\$0.00	
=====							
GRAND TOTAL		\$15,000.45	\$10,923.72	\$34,608.83	\$15,075.00	\$75,608.00	