

STONE CONSTRUCTION SERVICES, INC.
MATERIAL USE REPORT

RUN DATE 05/25/2006

Page 1 of 4

ESTIMATE: Kitchen Remodel

FOR: Craig Mac

Kathy Mac

ESTIMATED BY: MCS

MATERIAL DESCRIPTION	QTY	UOM	ROOM	ITEM DESCRIPTION
1/4" Protective floor sheeting (Masonite or Equivalent)	440.00	SF	1	1/4" Protective floor covering
5 Ton jack rental	1.50	DAY	1	T/O 8' int. L.B. wall, add header flush with ceiling
Pickup/Return of rental equipment, (@ 1 HR./TRIP)	1.50	HR	1	T/O 8' int. L.B. wall, add header flush with ceiling
1" x 4" S&B, fir, 8'	90.00	LF	1	2" x 12" @ 16" O.C. floor joist system, complete
2" x 4" S&B, fir, 8'	288.00	LF	1	T/O exterior opening for new window, reframe over 41 SF
	85.00	LF	1	T/O 8' int. L.B. wall, add header flush with ceiling
	240.00	LF	1	T/O exterior opening for new window, reframe 21 to 30 SF
	33.00	LF	1	2" x 4" x 8' int. L.B. wall = studs/nails
	24.00	LF	1	2" x 4" interior N.L.B. wall tie in to existing 8' wall
	115.50	LF	1	12" x 12" bulkhead or soffit
2" x 4" S&B, fir, 12'	480.00	LF	1	Frame skylight well, 4' wall, dbl flare up to 96 SF of wall area
	9.00	LF	1	2" x 4" x 8' int. L.B. wall = studs/nails
2" x 12" S&B, fir, 12'	147.00	LF	1	2" x 12" @ 16" O.C. floor joist system, complete
4" x 8" S&B, fir, 8'	48.48	LF	1	T/O exterior opening for new window, reframe over 41 SF
	11.00	LF	1	T/O 8' int. L.B. wall, add header flush with ceiling
	40.40	LF	1	T/O exterior opening for new window, reframe 21 to 30 SF
1/2" x 4' x 8' plywood, CDX	120.00	SF	1	2" x 12" @ 16" O.C. floor joist system, complete
3/4" x 4' x 8' plywood, CDX	12.00	SF	1	1/2", 5/8" or 3/4" plywood underlayment patch at wall removal
1/2" x 4' x 8' MDF board	320.00	SF	1	1/2" MDF board underlayment
3/4" x 4' x 8' MDF board	12.12	SF	1	1" MDF seat for BAY / BOW window

STONE CONSTRUCTION SERVICES, INC.
MATERIAL USE REPORT

RUN DATE 05/25/2006

Page 2 of 4

MATERIAL DESCRIPTION	QTY	UOM	ROOM	ITEM DESCRIPTION
1/2" x 6" beveled cedar (4 3/4" exp.) TK				
	236.64	SF	1	Patch siding around new window or door, 1/2" x 6" bev cedar

Shims & screws, wood window(s) over 6' 0" x 5' 0"				
	1.00	EA	1	6' 4" x 5' 0" bay, 30 degree, XOOX, primed w/screens

1.5" Galv. screw, 1 per 1.5 LF of frame				
	16.00	EA	1	2' x 4' DG, vinyl, low-E openable
	16.00	EA	1	8' 0" x 4' 0" PF, white, low-E

8' 0" x 4' 0" PF vinyl frame				
	1.00	EA	1	8' 0" x 4' 0" PF, white, low-E

6' 4" x 5' 0" XOOX Bay w/screen				
	1.00	EA	1	6' 4" x 5' 0" bay, 30 degree, XOOX, primed w/screens

Copper roof system, to 96" wide				
	1.00	EA	1	6' 4" x 5' 0" bay, 30 degree, XOOX, primed w/screens

2' 0" x 4' 0" Vinyl frame, openable				
	2.00	EA	1	2' x 4' DG, vinyl, low-E openable

Shims & screws, per door, interior passage				
	1.00	EA	1	6' 0" x 6' 8" PH, 1/2 luv, fir, w/hrdwr & trim
	1.00	EA	1	2' 8" x 6' 8" PH, PKT, flush, hc, birch, w/hrdwr & trim

2' 8" x 6' 8" Fish, Birch, Pckt w/hrdwr/trim				
	1.00	EA	1	2' 8" x 6' 8" PH, PKT, flush, hc, birch, w/hrdwr & trim

6' 0" x 6' 8" Bf, 1/2 luv, fir, w/trim				
	1.00	EA	1	6' 0" x 6' 8" PH, 1/2 luv, fir, w/hrdwr & trim

6" wood (OAK) S. Door threshold, 6'				
	6.60	EA	1	1" x 5" red/white oak threshold, 6', cut/beveled to fit, unfinished

12" x 50' x 28 Ga. Galv. roll stock				
	48.00	LF	1	Galvanized 28 ga. flashing on exterior of new skylight
	24.00	LF	1	Roof to wall flashing, 12" stock, include siding cut & reail

Recessed can light			MAA \$40.00	
	12.00	EA	1	110v recessed can over 30' from panel MA @ \$40.00

Pulls, door & drawer, MAA @ \$ 7.50 ea				
	34.00	EA	1	Pulls, door & drawer, installed, MAA @ \$ 7.50

Towel bar, 18" to 24" chrome, MAA @ \$7.50				
	1.00	EA	1	F&I towel bar, 18" to 24" chrome, MAA @ \$7.50

STONE CONSTRUCTION SERVICES, INC.
MATERIAL USE REPORT

RUN DATE 05/25/2006

Page 3 of 4

MATERIAL DESCRIPTION	QTY	UOM	ROOM	ITEM DESCRIPTION
Paper towel dispenser, MAA @ \$7.50	1.00	EA	1	F&I paper towel dispenser, MAA @ \$7.50
7/16" x 1 1/2" standard casing				
	18.70	LF	1	1" x 5" surround & 7/16" x 1 1/2" casing on door
	39.60	LF	1	1" x 6" surround & 7/16" x 1 1/2" casing on BAY / BOW window
	48.40	LF	1	1" x 5" surround & 7/16" x 1 1/2" casing on window
1" x 5" CVG, S4S (10' PC)				
	18.70	LF	1	1" x 5" surround & 7/16" x 1 1/2" casing on door
	35.20	LF	1	1" x 5" surround or banding in skylight well
	48.40	LF	1	1" x 5" surround & 7/16" x 1 1/2" casing on window
1" x 6" CVG, S4S (10' PC)				
	39.60	LF	1	1" x 6" surround & 7/16" x 1 1/2" casing on BAY / BOW window
2" x 6" Galv. joist hanger				
	10.00	EA	1	T/O 8' int. L.B. wall, add header flush with ceiling
2" x 12" Galv. joist hanger				
	18.00	EA	1	2" x 12" @ 16" O.C. floor joist system, complete
6d casing, bright				
	2.40	LB	1	2" x 12" @ 16" O.C. floor joist system, complete
1" Galv. joist hanger nail				
	0.10	LB	1	T/O 8' int. L.B. wall, add header flush with ceiling
	0.12	LB	1	2" x 12" @ 16" O.C. floor joist system, complete
1 1/2" Galv. roofing nails				
	0.48	LB	1	Galvanized 28 ga. flashing on exterior of new skylight
	0.24	LB	1	Roof to wall flashing, 12" stock, include siding cut & renail
7d Galv. siding nail				
	4.64	LB	1	Patch siding around new window or door, 1/2" x 6" bev cedar
1 1/4" ring shank underlayment				
	6.40	LB	1	1/2" MDF board underlayment
	0.24	LB	1	1/2", 5/8" or 3/4" plywood underlayment patch at wall removal

STONE CONSTRUCTION SERVICES, INC.
MATERIAL USE REPORT

RUN DATE 05/25/2006

Page 4 of 4

MATERIAL DESCRIPTION	QTY	UOM	ROOM	ITEM DESCRIPTION
16d green vinyl coated				
	0.48	LB	1	T/O exterior opening for new window, reframe over 41 SF
	0.10	LB	1	T/O 8' int. L.B. wall, add header flush with ceiling
	0.40	LB	1	T/O exterior opening for new window, reframe 21 to 30 SF
	1.92	LB	1	Frame skylight well, 4' wall, dbl flare up to 96 SF of wall area
	2.40	LB	1	2" x 12" @ 16" O.C. floor joist system, complete
	0.06	LB	1	2" x 4" x 8' int. L.B. wall = studs/nails
	0.02	LB	1	2" x 4" interior N.L.B. wall tie in to existing 8' wall
	0.42	LB	1	12" x 12" bulkhead or soffit

Single bulb recessed fixture, MAA @ \$75.00

	12.00	EA	1	Recessed fixture MA @ \$75.00 fixture, installed
--	-------	----	---	--

Drafting paper

	4.00	SHT	1	Plans.....Kitchen
--	------	-----	---	-------------------

Exterior Butyl caulking (30 LF)

	3.30	LF	1	Caulking around windows/doors, joints
--	------	----	---	---------------------------------------

Kraft paper, 36" x 166 LF roll (500 SF)

	360.00	SF	1	Floor & wall protective covering, interior demo work
--	--------	----	---	--

2 mil plastic, 10' x 50 LF roll (500 SF)

	360.00	SF	1	Floor & wall protective covering, interior demo work
--	--------	----	---	--

1" Masking tape

	6.00	ROLL	1	Floor & wall protective covering, interior demo work
--	------	------	---	--
